

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 166

For corners in

GLADWIN
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>1W</u> | <u>1-5</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:18 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | ● | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, MARK R. ROBISON, in a field survey on April 17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|--|---|
| 1877 T. Gale Merrill Set Post Wit.-(1)S82E 20 links 14" Elm (2)S48W 20 links 14" Black Ash | 1960 Edmands Eng.-working dwg. |
| 1960 Edmands Eng.-Railroad maps Set iron Wit.-(3)N45E 47.5' Fence Corner (4)N82W 26.80' Corner Gate Post (5)S60W 22.8' - 6' high 4" Pipe | 1975 Lapham Found 5/8" rod Wit.-same as (3),(4)&(5) |
| | 1978 Lapham survey |
| | 1988 Lapham survey |

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/25/97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 1/2" x 8" rerod 1.5 ft. below surface over 1/4" x 2" x 14" flat iron in driveway to west on extended line of county roads North & East. Found capped iron South 33.00' referencing 1978 Lapham survey #782010. Found 1/2" rerod bent and loose 33'+/- West referencing 1988 Lapham survey #877644. Found (5); pipe at slight angle, measured 22.7', recorded 22.80. Set Gladwin County Re-mon from found 1/2" rerod and witness (5) and survey 782010.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: Corner common to Sections 10, 11, 14 & 15
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458


Witnesses:
South Capped Iron 33.00'
N40E Corner Post, nail & tag, 57.73'
N75W 4" x 7' Metal Post 24.75'
N10W Cluster of Maples 4"-8", nail & tag, 20.65'

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-7-97