



Liber: C1 Page: 866

STATE OF MICHIGAN - GLADWIN COUNTY
RECORDED



Ann Manning - REGISTER OF DEEDS
11/30/2016 1:38 PM

Receipt #: 104426 Page: 1 of 2
30.00 CORNER

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson

Field Survey Date: April 3, 2014

For corner(s) in: Gladwin County

Original Public Land Survey Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Corner

Corner Code

S	1	T	19N	R	01W	12
S		T		R		
S		T		R		
S		T		R		

Protracted Public Land Survey Corner

Corner Code

S	12	T	19N	R	01W	L4
S		T		R		
S		T		R		
S		T		R		

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

12 – CS 1/16 corner section 1

L4 – Center ¼ corner section 12, T19N, R1W

– None

– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

12 – CS 1/16 corner section 1

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure. Position falls in North-South single strand wire fence and 50' South of fence to West.

L4 – Center 1/4 corner section 12, T19N, R1W

Set a stamped 2" aluminum cap on 5/8" X 34" rebar at the intersection of 1/4 lines per BLM standard procedure. North-South single strand fence is 7' East.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

12 – CS 1/16 corner section 1

a stamped 2" aluminum cap on 5/8" x 34" rebar

N80°E 32.23' to set nail & tag in N. side 17" R. Maple
S05°W 8.52' to set nail & tag in E. side 15" R. Maple
N83°W 16.40' to set nail & tag in S. side 20" R. Maple
N46°W 17.82' to set nail & tag in NE. side triple 12" R. Maple


Set blue post with location tag 1' Southwest

L4 – Center 1/4 corner section 12, T19N, R1W

a stamped 2" aluminum cap on a 5/8" X 34" rebar.

N84°E 12.82' to set nail & tag in S. side 10" W. Pine
S40°E 19.60' to set nail & tag in SW. side 18" W. Pine
S80°W 39.90' to set nail & tag in N. side 12" Spruce
N32°W 11.28' to set nail & tag in SW. side 14" W Pine

Set blue post with location tag 1' East.



Certifying Surveyor's Name

November 28, 2016

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

