



Liber: C1 Page: 870

STATE OF MICHIGAN - GLADWIN COUNTY
RECORDED



Ann Manning - REGISTER OF DEEDS
11/30/2016 1:38 PM

Receipt #: 104426 Page: 1 of 2
30.00 CORNER

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson Field Survey Date: February 25, 2014
For corner(s) in: Gladwin County

Original Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Corner			Corner Code
S	1	T 19N R 01W	8
S	1	T 19N R 01W	11
S		T R	
S		T R	

Protracted Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6		5		4		3		2		1			2
3														3
4	7		8		9		10		11		12			4
5														5
6	18		17		16		15		14		13			6
7														7
8	19		20		21		22		23		24			8
9														9
10	30		29		28		27		26		25			10
11														11
12	31		32		33		34		35		36			12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

<u>8</u> – CW 1/16 corner section 1	<u>11</u> – SW 1/16 corner section 1
– None	– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

8 – CW 1/16 corner section 1

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedures.

11 – SW 1/16 corner section 1

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

8 – CW 1/16 corner section 1

a stamped 2" aluminum cap on 5/8" x 34" rebar

N36°E 22.68' to set nail & tag in SE. side 12" W. Pine
S60°E 53.09' to set nail & tag in N. side 18" W. Pine
S01°W 24.59' to set nail & tag in E. side 10" R. Maple
S50°W 6.05' to set nail & tag in NW. side 11" R. Maple


Set blue post with location tag 1' Northeast

11 – SW 1/16 corner section 1

a stamped 2" aluminum cap on 5/8" X 34" rebar

N87°E 31.83' to set nail & tag in N. side 16" W. Pine
S02°E 44.65' to set nail & tag in W. side 6" R. Maple
West 5.66' to set nail & tag in S. side 12" W. Pine
N03°W 6.01' to set nail & tag in W. side 10" W. Pine

Set blue post with location tag 1' Northeast



Certifying Surveyor's Name

November 28, 2016

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

