

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 45 N. R. 44 W.	I-9-10 001
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S. R. _____ E. W.	C. C. on State
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	Line
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Register's Office } ss.  
Gogebic County }

Received for record the  
21<sup>st</sup> day of MAY  
A. D. 1993 at 3:10 o'clock  
P. m., and recorded in  
Liber 4 of CORNERS  
on page 234  
*Betty L. Drahn*  
Register of Deeds  
REGISTER OF DEEDS STAMP AND  
FILING NUMBER

Closing corner 26 & 27 on State line; T.45N., R.44W.

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on November 10 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

## A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 24, 1851.  
Original bearing trees:

Yellow Birch	10"	N.58°E.	13 links	8.58 feet
Sugar	8"	N.50°W.	10 links	6.60 feet

## B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No evidence of original corner or bearing trees recovered. Corner position re-established on line between and proportionate distance from Mile Corner 17 and M.C. 16½ + 49.2 feet.

PEER GROUP APPROVED

*Richard L. Drahn* 1/20/94  
COUNTY REPRESENTATIVE

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2½" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap, stamped to read: T.45N., R.44W.; C.C.; S-26, S-27; MI.WI.; State Boundary; 1992; R.L.S. 21564. From which I have established the following new blazed and scribed bearing trees:

13"	White Ash	N.58°W.	10.49 feet
11"	Basswood	N.81°E.	10.82 feet
9"	White Ash	S.73°W.	19.07 feet
6'	steel rail	N.12°E.	1.7 feet
3/4"	iron pipe	N.81°W.	10.65 feet

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Richard L. Drahn DATE 5-04-93

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

U.S.F.S. ST-17

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564