

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic county }

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|--------------|
| 1. Public Land Survey | T <u>45N</u> R <u>46W</u> | <u>K-3-4</u> |
| | T _____ R _____ | |
| | T _____ R _____ | <u>003</u> |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous | S _____ T _____ R _____ | |
| Property in Sec. | S _____ T _____ R _____ | |

Received for record the
11TH day of JUNE

A. D. 1997 at 10:45 o'clock

A m., and recorded in

Liber 6 of CORNER

on page 152

Colleen M. Kibak Deputy

Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Closing Corner, Secs. 11 & 12; T.45 N., R.46 W.
on Mich.---Wisc. State Line

I, Richard L. Drahn in a field survey on May 22, 19 97,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on June 28, 1851. Original B.T.s --- Fir
6" N.85 E. 38 links (25.08') --- Y. Birch 14" N.32 W. 9 links (5.94') ---

Corner positioned 2.52 chains N.74 W. from Mile Corner #5½.

Research form on file with Gogebic County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains
of the Yellow Birch bearing tree. It is now the root remains of a very
large Yellow Birch stump, the only large old growth birch remains re-
covered in the area. No evidence remains of the original Fir B.T.
The 2.52 chain distance S.74 E. to Mile Corner #5½ is in accordance
with the field notes of the original survey.

PEER GROUP APPROVED


Richard L. Drahn 6/10/97

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 48" solid aluminum marsh rod with a
3½" aluminum cap stamped to indicate the corner and the following new B.T.s:

- | | | | |
|-----|-----------------|---------|-----------|
| 8" | Red Maple | N.70 W. | 28.63 ft. |
| 9" | Black Ash | N.11 E. | 33.22 ft. |
| 14" | Black Ash | N.86 E. | 40.81 ft. |
| 6' | Steel sign rail | N.09 E. | 2.56 ft. |



Signed by Richard L. Drahn

Date June 7, 1997

Surveyor's Michigan License No. 21564