

SURVEY & REMONUMENTATION

JAN 05 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County }

For corners in
Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

T46NR47W

T R

T R

T R

2. Property Controlling S
in Section S

T R

T R

3. Miscellaneous S
Property in Sec. S

T R

T R

4. Lot No. , Recorded Plat

5. Private Claims

Meander Corner common to Sections 11 and 14.

I, John R. Garske, in a field survey on April 26, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and / or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Received for record the
2ND day of JUNE
A. D. 1900 at 10:20 o'clock
A. m., and recorded in
Liber 7 of CORNERS
on page 356
Cheryl Rupp, Reg.
Register of Deeds
Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7						9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	15			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and / or subsequent restoration:

Original survey by William Ives in 1848.

Original Corner: Wood post

Original Bearing Trees: 14" Fir S 59° E 8 Links
6" Maple N 65° E 47 Links

B. Description of corner evidence found and / or method applied in restoring or re-establishing corner:

I found an ancient fenceline extending from the section corner common to Sections 11, 12, 13, and 14, West to intersect with the Montreal River. I also located another semi-obliterated fenceline that wandered Westward and intersected the river at a point 50 feet Southeast of the determined corner location.

Record research on file.
(see sketch on back)

PEER GROUP APPROVED
Richard L. Decker 5/24/00
COUNTY RECORDATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I set a 30" aluminum Bernsten monument to witness the meander corner which fell in the river 34.10 feet West, from which I established the following witnesses:

8" Spruce	N 83° E	47.53 Feet
6" Balsam	N 19° E	23.35 Feet
16" Spruce	S 41° E	29.94 Feet
4' Steel Sign Post	N 70° E	1.72 Feet

Signed by

John R. Garske

Date




Surveyor's Michigan License No. 28410
FB # 251, page 15 & FB # 213, page 126

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

SURVEY &
 REMONUMENTATION
 JAN 05 2001
 SECTION

Meander Corner common to Sections 11 & 14,
 T 46 N, R 47 W.



Scale: 1" = 300'

