

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code # R28

1. Public Land Survey

T46N R47W

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

2. Property Controlling  
in Section

S\_\_\_ T\_\_\_ R\_\_\_

S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous  
Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_

S\_\_\_ T\_\_\_ R\_\_\_

LM-9

KLB

009

Register's Office  
Gogebic County

Received for record the

2<sup>nd</sup> day of JUNE

A. D. 1900 at 10:20 o'clock

A m., and recorded in

Lib. 7 of CORNERS

on page 359

Cheryl Rupp, Dep.  
Register of Deeds

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Meander corner on east bank Montreal River to Sections 24 and 25, T46N,  
R47W.

I, John R. Garske, in a field survey on May 24, 2000 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1  
and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4  
and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed  
below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

This corner was set by William Ives Sept. 1848. He set a wooden post to which he established the following witnesses:

15" White Pine	N77°E	46 links
7" Fir	S68°E	58 links

SURVEY &  
REMONUMENTATION

JAN 05 2001

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

I found a original bearing tree (White Pine). The remains consist of a hollowed out stumped with scribing clearly visible. I reset  
the meander corner from G.L.O notes at record bearing and distance.

Record Research on file.

PEER GROUP APPROVED


Richard L. Dean 5/24/00

COUNTY RECORDED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set 3" x 30" aluminum Bersten monument with a stamped cap with the following witnesses:

6" Cherry	S55°E	35.00 feet
5" Elm	S87°E	27.07 feet
10" Balsam	N52°E	50.44 feet
Steel sign Post	S68°W	0.88 feet



Signed by

John R. Garske

Surveyor's Michigan License No. 28410

Date

5/24/00

MONTREAL  
RIVER

MEANDER CORNER @ EASTERN EDGE  
OF MONTREAL RIVER, SECTION 24 & SECTION 25,  
TOWNSHIP 46 NORTH, RANGE 47 WEST

24  
25  
SET BERNSTEN MONUMENT  
AT MEANDER CORNER POSITION

N89°25'19"E  
1841.24(M)  
1780.68' (GLD)

24.19  
25.30

SCALE : 1" = 200'

SURVEY &  
REMONUMENTATION

JAN 05 2001

SECTION