

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of SEPTEMBER  
A. D. 1997 at 10:45 o'clock  
A. m., and recorded in  
Liber 6 of CORNERS  
page 209  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code =#

Public Land Survey

T 47N R 44W

G-1

T R

T R

T 48N R 44W

G-13

Property Controlling  
In Section

S T R

Miscellaneous  
Property in Sec.

S T R

Lot No. , Recorded Plat

Private Claims

Section Corner 3, 4, 33 & 34; T.47-48 N., R.44 W.

Richard L. Drahn in a field survey on September 10, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 11, 1847. Original B.T.s --- Hemlock 20" N.80 E. 45 links (29.70') --- Hemlock 14" N.74 W. 40 links (26.40') --- Sugar 8" S.45 E. 20 links (13.20') --- Hemlock 10" S.40 W. 25 links (16.50') ---

Corner restored on 9/12/72 by Donald D. Lappala (12585) from the remains of the three original Hemlock B.T.s and the stump hole of the Sugar B.T.. He set a 2" X 60" iron pipe monument with a 3" stamped brass cap and the following new B.T.s: --- 8" (10" dead) Sugar Maple N.25 E. (N.24 E.) 27.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

--- 7" (9") Red Maple S.32 E. (S.30 E.) 45.7' (45.70') --- 4" (5" dead) Sugar Maple S.60 E. (S.62 E.) 19.0' --- Metal sign post N.02 W. (N.01 W.) 2.3' (2.33') ---

Corner recorded in USFS Liber, Page Z-13 on 12/9/74.

Recovered the corner as described and the bearing trees as indicated in parentheses above. Beavers have flooded out the first and third original B.T.s and stump holes are all that remain of the second and fourth B.T.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


From the above described monument I established the following new B.T.s:

5" Red Maple S.66 W. 21.18'

5" Red Maple S.26 W. 44.19'

PEER GROUP APPROVAL

Richard L. Drahn 9/17/97  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 15, 1997

Surveyor's Michigan License No. 21564

USFS A-13  
Z-13