

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
14th day of MAY
A. D. 1998 at 3:30 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 390
Bramona Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

For corners in
Gogebic

(County)

Located in: Corner Code #

Section 34 48N 45W H-11

1. Public Land Survey

T R
T R
T R
T R
T R
T R
T R
T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner sections 27 & 34, T48N, R45W

I, John R. Garske, in a field survey on December 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by Austin Burt, D.S. in 1848
He set a wood post from which:
W. Pine 16" S55°W 13 links
Cedar 8" N15°E 7 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence exists. I established the corner by single proportionate method between the N.W. corner and the N.E. corner of said section 34, in accordance with the original government notes. The position lines up with the centerline extension of a north-south trail. Corner falls at southerly toe/slope of railroad grade and is 30.6 feet perpendicular distance off centerline of railroad tracks.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" diam. x 36" long alum pipe with a 3 1/4" diam. alum cap stamped to identify the corner, from which:


6' steel sign rail	North	3.1 feet
5" maple	S80°W	6.32 feet
7" B. Ash	S12°W	34.23 feet
5" B. Ash	S35°E	27.32 feet
10" cheery	N74°E	32.03 feet
E RR Tracks	North	33.2 feet

513

STATE OF MICHIGAN
JOHN R. GARSKE
LAND SURVEYOR

Signed by _____
Surveyor's Michigan License No. 28410

Date _____



V-15

390