

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

For corners in

Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

Section T1 R48N 46W A-12
T48N R47W M-12
T R
T R
S T R
S T R
S T R
S T R

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter corner common to sections 31 & 36, T48N, R47W & R46W

I, John R. Garske in a field survey on May 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Township Survey by William A. Burt, D.S.1847.
Original bearing trees: Lynn 7" S57°-05'-5links, & Lynn 6"-N68°W-32links.
1977-Corner established by Ewart Muller, RLS 15408 by single proportion on the range line and recorded liber 1, pg. 341 he set a 1" x 3' iron pipe from which;

Witnesses;

Chisled "+" in rock	Due West	55.60 feet
8" aspen	S50°E	45.73 feet
Fence post	N50°W	66.41 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a bent pipe at Mullers corner position. I reset a standard Bernsten Aluminum pipe monument at the corner from two of Mullers ties, the boulder and aspen and additional ties from our survey files from a 1989 survey of the Ironwood Township Landfill.

(Research on file)

DEER GROUP APPROVED
Richard L. Drahm 7/20/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset 30" x 2 1/2" alum. monument with a 3 1/4" dia stamped alum. cap from which:		
Sign rail	S60°E	1.12 feet
Chiseled "+" in boulder	S80°W	56.00 feet (55.60')
8" W. Birch	S52°E	47.05 feet
Twin 3" maple	S76°E	49.15 feet



Signed by

Surveyor's Michigan License No.

Date

7/20/99