

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDEDLAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

30 DEC 99 3:39 P.M.

KARON ANDERSON
REGISTER OF DEEDS

FOR CORNERS IN

GRAND TRAVERSE
(COUNTY)

LOCATED IN: CORNER CODE C-10.

1. Public Land Survey W¹ cor SEC 29 , T 26 N R 11 W
Blair Township

G.T. County Code 99-23

I, Corey J. Hughes, in a field survey performed in Oct-Dec, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner point mentioned in lines 1 and 2 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines

3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

1839 GLO survey set 1/2 post and wit; 12 Beech S66E 16 lks, 11 Sugar N29W 31 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1960 PSA survey for CoPC indicated a concrete monument set.

1999 GCES found a concrete monument over cedar post remains with 3 cobble stones. Corner is fence E/W and woods line N/S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position was accepted as an existing and accepted corner, in agreement with the occupation. The concrete monument was replaced with county Remonumentation pipe and cap. Wit:

spk in 12in Maple S60W ~ 19.6ft
spk in 18in Maple N83E ~ 9.24ft
spk in 12in Maple S30E ~ 27.72ft
spk in 12in twin Basswood S06E ~ 26.17ft

SURVEY &
REMONUMENTATION

MAR 22 2000


SECTION

UNANIMOUSLY ACCEPTED BY THE
GRAND TRAVERSE COUNTY PEER
REVIEW GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC
ACT 345 OF 1990 AT A MEETING
HELD ON 10/27/99

ROBERT F. MITCHELL, P.S., CLERK

Corner approved by the Grand Traverse County Peer Review Group on October 27, 1999

Signed by



Date 12/29/99

Corey J. Hughes, Michigan P.S. License No. 20706

