

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. R. 10 W.	I-7; J-7
2. PROPERTY CONTROLLING IN SECTION	14, T. 27 N. R. 10 W.	5; 8
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S. R. E. W.	
4. LOT NO.	, RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 30, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restorations

C. (CONTINUED)

8  
Fd. Buggy Axle & set cedar  
post w/loc. tag  
15" Oak N27°E 77.1  
20" Oak N76°E 44.8  
8" Maple S23°W 28.4

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-7 Found conc. sub'n. monument at position of previously found old 1 1/4" pipe. Fits old survey by E.P. Waterman, subsequent surveys by Walt Fraser, & is now a plat monument ("English Woods").
- J-7 Found rerod by R.L.S. L.Czubek, which is a perpetuation of 1/4 corner by Waterman wit's. dated Dec. 1907, who restored corner from original U.S.B.T.'s.
- 5 Established 1/16 corner per standard B.L.M. instructions.
- 8 Found & accepted buggy axle for W 1/16 on E-W 1/4 line, Sec. 14, per E.P. Waterman survey of Sec. 14 dated 1907.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7	J-7	5
Fd. Conc. Mon. & set cedar post w/loc. tag	Fd. 5/8"x24" rerod w/RLS Cap #12581 & set DNR mon. & cedar post	Drove 3/4"x36" pipe & cedar post w/loc. tag
18" Oak S45°E 52.82	36" W. Pine Stp. N05°W 27.6	12" Oak N29°E 72.2
24" Oak N71°E 44.04	30" W. Pine Stp. N63°W 36.0	3" W. Pine S49°E 57.2
1/2" pipe (lot corner) N86°W 19.95	24" Twin Oak S34°E 10.14	10" Oak S14°W 9.1
	12" Oak S46°W 43.07	12" Oak N18°W 57.7
	12" R. Pine N68°W 30.75	

SIGNED BY Carl F. Roser 4-28-77 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

GRAND TRAVERSE COUNTY