

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	B7
	T R	
	T R	
2. Property Controlling in Section	S 18 T 51N R 36W	13
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on B7 09/27/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B7) Quarter corner common to Sections 18 and 19. 1848 - Established by S.W.Higgins Deputy Surveyor
on the Section line between Section corner 40.00 chains east and Section corner 40.52 chains west.
Set post. Hemlock 24" S10W 22 links, Maple 12" N30W 41 links.

(13-Sec. 18) Southeast 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the corner on the Section line between Section corner
2624.77' east and Section corner 2658.89' west, being proportionate to the original record.

(13-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16
corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" Maple N30E 19.15' mrkd "1/4S NBT"
7" Hemlock S45E 17.25' do
twin 4" Hemlock S29W 42.55' do
double 6" Sugar N52W 10.7' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Spruce N42W 23.35' mrkd "1/16S BT"
7" Maple N41E 20.3' do
11" Hemlock N72E 18.05' do
3" Maple S61W 10.8' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/06/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

