

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	B9
	T	
	T	
2. Property Controlling in Section	S T	
	S T	
	S T	
3. Miscellaneous Property in Sec.	S T	
	S T	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/13/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B9) Quarter corner common to Sections 19-30. 1974 - Reestablished by A.O.Enger RLS #13581 "in road  
junction at record distance from west 42.960 ch. on line between section corners Mag. bearing N89  
deg. 53'15"W." Set 1"IDx24" I.pipe with 4" alum. cap. Nail in power pole N65W 56.10', Nail in fence  
cor. post S19E 70.85', North sign post road sign S76W 31.23'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B9) The 1974 monument was found disturbed, bent over by road grader. The bottom portion of the pipe  
was found undisturbed and in a vertical position. The 1974 witnesses are no longer present though I  
note that the power pole currently in place, seemingly newer than 1974 is located at the record  
bearing and distance. Removed the 1974 monument and replaced it with a new one, buried 7" below the  
road surface. The corner position falls at the east edge of the graveled Pike Lake Road and at the  
north edge of the graveled N. Laird Road and in line with a fence to the west. I found the monument  
to be 42.897 chains east of corner A9 and 8.5' north of a straight line between Section corners A9  
and C9. Accepted the monument as a careful and faithful reestablishment of the position of the  
original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap  
buried to 7" below the graveled road surface.  
Set measuring nail with MDNR tag in the side of:  
11" Spruce N60E 57.9' mrkd "1/4S NBT"  
5" Maple S27E 85.8' do  
7" Sugar S47W 65.9' do  
Power pole 5135 19L25 N60W 56.1'  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 06/02/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities