

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	C6
	T 51N R 36W	B5
2. Property Controlling in Section	T R	
	T R	
	T R	
3. Miscellaneous Property in Sec.	T R	
	T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on C6 09/13/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17 and 18. 1959 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" I.D. I.pipe with 4" brass cap. 11" White Pine N52E 40 links, 6" Sugar Maple S54W 14 links.

(B5) Quarter corner common to Sections 7 and 18. 1959 - Remonumented by Billy D. Buckler RLS from stump of Hemlock B.T. N85E 08 links, in poor condition, scribing plain. Set 1" pipe with 4" brass cap. 20" Cedar S89E 52 links, 22" Sugar Maple S19W 5.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) Found the 1959 monument in good condition and at record bearing and distance from the 1959 witnesses, both in good condition. Measured to Section corners north and south to verify the position of the monument and accepted same as a careful and faithful reestablishment of the position of the original corner.

(B5) Found the 1959 monument in good condition and at record bearing and distance from the Cedar NBT SE, in good condition with scribing visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
17" W.Pine N54E 27.1' old blazes (1959 NBT)
7" Sugar S62W 9.55' do do
4" Cedar S33E 9.85' mrkd "1/4S NBT"
6" Hemlock N03W 6.0' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(B5) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
20" Cedar S87E 35.7' old marks 1959 NBT
7" Y.Birch N27E 7.85' mrkd "1/4S NBT"
7" Maple S39E 16.4' do
10" Maple S73W 3.1' do
Cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/06/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

