

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	K1
	T R	
	T R	
2. Property Controlling in Section	S 1 T 51N R 36W	6
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 01/16/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K1) Corner common to Sections 1-2 T51N-R36W and Sections 35-36 T52N-R36W. 1963 - Billy D. Buckler
RLS replaced a found 1.5" dia. Iron pipe with a 1" iron pipe and 4" alum. MI Dept. of Conservation
cap. Two Y.Birch stumps were found, rotted but at proper bearing and distance [for orig. bearing
trees]. 12" Cedar S33W 48.5 links, 14" Hemlock S87E 61.5 links.

(6-Sec. 1) Northeast 1/16 corner, Section 1. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K1) Found the 1963 monument disturbed, knocked over by a fallen tree. Reset the 1963 monument at
the record position as determined from the 1963 bearing trees, now both down.

(6-Sec. 1) Established the position for the corner at the intersection of straight lines connecting
opposite 1/16 corners. The position for the corner falls at the center of a 14" Hemlock.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K1) Set 1"IDx36" I.pipe with 4" MI Dept. of
Conservation cap (the 1963 mon. of record).
Set measuring nail with MDNR tag in the side of:
18" Maple S85W 78.95' mrkd "S2 NBT"
7" Y.Birch S58W 57.85' do
6" Balsam S38E 58.15' "S1 NBT"
6" Maple S82E 75.25' do
1.5"I.D.x3.5' tall iron pipe N77W 0.4'
N=231505.754, E=7860701.763

(6) The position for the corner falls at the
center of a 14" Hemlock.
Blazed, scribed "1/16", and painted the Hemlock
on four sides.
No other monumentation was placed and no witnesses
to the corner position were taken.
N=231058.813, E=7861897.390

Bearings are magnetic. Coordinates are MCS83 in meters.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 02/07/2013

For the Michigan Department of Natural Resources, Forest Resources Division

