

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 36W T T	E12 (GCDB 300140)
2. Property Controlling in Section	S 33 T 52N R 36W S S	F12 (GCDB 340140)
3. Miscellaneous Property in Sec.	S S	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/08/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1963 - Remonumented in the original position by Billy D. Buckler RLS at the position of two wood stake bottoms found at record bearing and distance from an original Y.Birch BT 10" N80°E 24 links, badly rotted. Set 1"ID I.pipe with 4" aluminum cap. 8" Cedar S45°W 29 links, 10" Cedar N38°W 27 links.

(F12) Center of Section 33. 2002 - John Garske PS of Coleman Engineering Company, established the position for the corner at the intersection of 1/4 lines. His survey maps of that date (Job #SI-02048) show that he set a 1-1/2" iron pipe and found an "erroneous 1/2" iron pipe" N57°29'11"E 80.23' distant. No witness trees noted.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) Found the 1963 monument in good condition and at record bearing and distance from the remaining 1963 NBT Cedar S45°W 29 links, now 12" with scribing visible. A sq'd cedar post was found adjacent. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(F12) Found a 1"ID iron pipe substantially at the intersection of straight lines connecting opposite 1/4 corners, in accord with the dimensions shown on the Coleman Engineering Company drawings. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Found 1"ID I.pipe with 4" alum. MI Dept of Conservation cap. Set measuring nail with MDNR tag in the side of:  
12" Cedar S48°W 19.65' old marks (1963 NBT)  
17" Hemlock N36°W 22.3' mrkd "1/4S NBT"  
9" Cedar N58°E 18.3' do  
11" Cedar S72°E 22.55' do  
E= 7855879.961 N= 232365.881

(F12) Found 1"ID I.pipe and set 2" alum. MDNR cap over the top of it. Found measuring nails with bottle caps in the sides of the following:  
17" W.Pine N86°W 13.85' which I marked "C1/4 BT"  
21" W.Pine N17°E 32.55' do  
15" W.Pine S78°E 23.4' do  
Set measuring nail/DNR tag in:  
5" Maple S07°W 4.8' do  
Set sq'd cedar post adjacent.  
E= 7856708.071 N= 232323.009

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum  
Coord. Ref.=NGS PID RL0502: N= 234995.272m. E= 7857774.766m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/20/2015

For the Michigan Department of Natural Resources, Forest Resources Division

