

LAND CORNER RECORDATION CERTIFICATE

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Stephan J. Szyszkoski

Field Survey Date: April 20, 2016

For corner(s) in: Houghton County

Original Public Land Survey Corner

Corner Code

a. S T 53N R 34W C9 (GCDB 200300)
 S T R
 S T R
 S T R

Property Corner

1/16 Corner Code

b. S 19 T 53N R 34W 16 (GCDB 160300)
 b. S 30 T 53N R 34W 2 (GCDB 160300)
 S T R
 S T R

| | | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M | 1 |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | 2 |
| 3 | | | | | | | | | | | | | | 3 |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | 4 |
| 5 | | | | | | | | | | | | | | 5 |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | 6 |
| 7 | | | | | | | | | | | | | | 7 |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | 8 |
| 9 | | | ● | | | | | | | | | | | 9 |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | 10 |
| 11 | | | | | | | | | | | | | | 11 |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | 12 |
| 13 | A | B | C | D | E | F | G | H | I | J | K | L | M | 13 |

Part A. Corner History

a.) Section corner common to Sections 19-20-29-30. 1846 - Deputy S.W.Higgins established the corner and set post. Spruce 13" N35°E 70 links, Cedar 16" S50°W 20 links. 1920 - P.A.Larsen, forester and surveyor, Set post from BTs Cedar and Spruce. No witnesses. 1966 - Billy D. Buckler RLS found a fence corner having fences running North and West, and from which distances South to River and North to 1/4 corner check with the record. He restored the corner position at the fence corner. Set 1" pipe with 4" brass cap. 20" Cedar S58°W 40.3', 10" W.Birch East 17.7'. Found no subsequent record.

b.) East 1/16 corner between Sections 19 and 30. Not previously monumented.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

a.) Found the 1966 monument, in good condition and at record bearing and distance from the 1966 witnesses: The W.Birch is down and rotted; the Cedar is standing, alive, 25" DBH, with two overgrown blazes facing the monument. The fence corner post w/barbed wire is now down on the ground, adjacent. Though I cannot definitely tie the monument directly to the original position, I presume that the fence corner found in 1966 perpetuated the 1920 Larsen position and thus, the original corner position.

b.) Established the position for the corner midway and on the Section line between Section corner 1365.94' East and Quarter corner 1365.94' West.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

(a.) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:

25" Cedar S63°W 40.7' old blazes 1966 NBT
 4" Elm S81°E 7.8' mrkd "S29 NBT"
 5" Y.Birch S22°W 18.45' "S30 NBT"
 8" Sugar N36°W 10.15' w/ KLA poster "S19 NBT"
 Set sq'd cedar post adjacent.
 E= 7873861.861 N= 243993.051

(b.) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 21" Y.Birch N84°E 8.0' mrkd "1/16S BT"

3" Sugar S40°W 3.7' do
 6" Sugar N65°W 14.9' do
 8" Sugar N14°W 14.1' do
 Set sq'd cedar post adjacent.
 E= 7873450.002 N= 244053.757

Bearings are magnetic. Coordinates are MCS83, NAD83(2011) Epoch 2010.00, in meters.

Coordinate Reference: NGS PID DL5986, E= 7882233.252 m. N= 259878.551 m.

Stephan J. Szyszkoski

06/29/2016

Professional Surveyor's License No.: 33986

page 1 of 1

Prepared By: S.J. Szyszkoski for the Michigan Dept. of Natural Resources, 427 N. US41 Baraga, MI 49908

