

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 13 T 55N R 33W S 11 T 55N R 33W S _____ T _____ R _____	3 SE-SE 1/64
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Stephan J. Szyszkoski, in a field survey on 3 07/28/2011
1/64 07/27/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 13) North 1/16 corner between Sections 13 and 14. Previously established by unknown persons.
Corner shown on the "Assessor's Plat of Tamarack Mill" L.2 of Plats, Page 132, dated 1980, Houghton
County Records. 2011 - R.W.Crampton PS #24591 reports a 2" iron pipe at the corner position with
distances north and south to adjacent K5 and K6 to be 1327.90' and 1330.87', respectively, and
forming an angle, clockwise from the north between these lines of 180 deg. 24'21". These dimensions
vary slightly from those given on the plat but are regarded as being more accurate.

(SE-SE 1/64 corner, Section 11) The Center of the SE1/4 of the SE1/4 of Section 11. Found no record
of prior monumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 13) Found a 2" iron pipe, set firmly, substantially at the position reported by Mr. Crampton:
1327.67' south of K5, 1330.81' north of K6, forming an angle between these lines, clockwise from the
north, of 180 deg. 28'06". I accepted the pipe as a careful and faithful determination of the
position of the corner.

(SE-SE 1/64) Found no monumentation at the corner position. Established the corner at the
intersection of straight lines connecting opposite 1/64 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Found 2"ID Iron pipe.
Set measuring nail with MDNR tag in the side of:
7" Maple N09E 7.6' mrkd "1/16S BT"
14" Sugar S51E 7.7' do
3" Maple S63W 5.75' do
5" Maple N63W 9.5' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

1/64 - Set 1"IDx32" I.pipe w/4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" Oak N16E 20.65' mrkd "1/64S BT"
6" Maple N69E 15.65' do
6" Poplar S21W 10.65' do
11" Maple in clump N43W 11.75' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/15/2011

For the Michigan Department of Natural Resources, Forest Management Division

