

OCT 08 1997

NOV 21 1997

COMMISSION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KEWEENAW  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 57N R 32W  
T 57N R 32W  
T 56N R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

C-12  
C-13 C-01

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE

County of Keweenaw } SS

Received for Record, the 29th

day of July A.D. 1997

at 10:00 o'clock A.M., and Recorded

in Liber 1 of LCR

on page 168

Marilyn Stenquist  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R.W. CRAMPTON, in a field survey on MAY 30, 19 85

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-12 WEST 1/4 CORNER-SET POST-

C-13 SOUTHWEST CORNER-SET POST-SUGAR 12 N18E 18, CEDAR 12 N55W 34.

Ratified by Peer Group  
In accordance with P.A. 345


Co. Rep. James M. Stubb

Date 7/29/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 WEST 1/4 CORNER-1 1/2" IRON PIPE FOUND AND SET WITH 4" BRASS CAP.

C-13 SOUTHWEST CORNER-1" IRON PIN IN CONCRETE FOUND AND SET WITH 4" BRASS CAP.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 THE 1 1/2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:  
18" MAPLE TREE N63 W 61.2', 5" OAK TREE S65 W 44.97',  
4" MAPLE TREE S48 E 46.62', 28" MAPLE TREE S9 W 60.27'.

C-13 THE 1" IRON PIN WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:  
4" CEDAR TREE N16 W 55.18', 4" ASPEN TREE S88 E 28.4',  
8" PINE TREE S50 E 27.16', 4" CEDAR TREE S13 W 17.0', EAST 11.89' TO NORTHEAST  
CORNER SECTION 6, T56N, R32W.

Signed by Robert W. Crampton

Date July 22, 1997

Surveyor's Michigan License No. 24591