

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Re-Mon Liber 1, Page 73

For corners in

Huron

(County)

Located In:

Corner Code #

1. Public Land Survey Sand Beach T16N R16E  
T R A-13  
T R B-13  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

6 NOV 97 10:26 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat  
5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 1834 G.L.O., H. Parke D.S.  
Post  
Hemlock 14", S28°W, 30 Links  
Do. 8", N31°E, 8 Links

County Surveyor Records - NONE, Unrecorded Surveys - NONE  
Co. Rd. Comm. Records - Pin in Post  
Survey Liber 3, Page 425 - 3/4" Re-Rod in Monument Box  
L.C.R.C. - NONE

B-13 1834 G.L.O., H. Parke D.S.  
Set quarter section post  
Hemlock 9", N61°W, 13 Links  
Do. 11", N34°E, 8 Links

Co. Surveyor Records - SEPT. 1865 Qr Stake, L.C.R.C. - NONE  
Co. Rd. Comm. Records - Axle, Unrecorded Surveys - NONE  
Survey Liber 3, Page 425 - Axle Shaft in Monument Box  
LAUGHLIN McDOWELL PLAT (Liber 3, Page 38) - shows corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13  
SW Cor, Section 31, T16N-R16E  
Found 3/4" Re-Rod in Monument Box  
Accepted as the best available evidence of original corner position  
(Intersection of Helena & Edwards Roads)

B-13  
S 1/4 Cor, Section 31, T16N-R16E  
Found Axle Shaft in Monument Box  
Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


A-13  
SW Cor, Section 31, T16N-R16E  
Found 3/4" Re-Rod in Monument Box  
N45°E 74.88' to Nail in SE Side of Power Pole  
S45°E 57.81' to Nail in NE Side of Cable Post  
N40°W 51.53' to S. Point of Conc. Project Marker  
West 2625.24' to S 1/4 Cor, Sec 36, T16N-R15E  
East 2623.54' to S 1/4 Cor, Sec 31, T16N-R16E

B-13  
S 1/4 Cor, Section 31, T16N-R16E  
Found Axle Shaft in Monument Box  
North 35.26' to W. End of 18" CMP  
N45°E 56.62' to E. End of 18" CMP  
South 34.98' to E. End of 36" CMP  
S45°W 44.52' to W. End of 36" CMP  
West 2623.54' to SW Cor, Sec 31, T16N-R16E  
East 2623.70' to SE Cor, Sec 31, T16N-R16E

igned by Charles S. Getz  
urveyor's Michigan License No. 25843

Date October 12, 1997

ER GROUP APPROVED AT  
ETING NOVEMBER 5, 1997.  
RLB



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985