

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron _____
(County) Located In: Corner Code #

1. Public Land Survey T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
2. Property Controlling S 34 T 42N R 31W 7
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims

Apr 12 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20 _____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 34) North 1/16 corner between Sections 34 and 35. Corner record dated Mar. 18, 1974 by A.O.Enger RLS, states: Established by transit and tape traverse on line between section corner 20.034 ch. N and 1/4 corner 20.034 ch. S. 1"ID I.pipe with 4" aluminum cap. R.Maple clump N24E 42.2', W.Spruce 8 S20E 65.4'. 1999: E.Kazianka, RLS placed an iron at a position intended to mark the corner during a survey in Section 35, after concluding that the Section corner I11 had been erroneously reestablished by A.O.Enger in 1974. Mr. Kazianka placed the monument at what he believed to be the proper position for the corner, should Mr. Enger's error be corrected.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7) The Iron County Remonumentation Program Peer Review group, in full possession of the facts involving the 1974 and subsequent surveys, concluded that the proper position for I11 is the position monumented in 1974 by A.O.Enger. The 1974 position had been subsequently used for several surveys in adjacent sections. Accordingly, I reestablished corner #7 herein described midway and on a line of mean true bearing between the 1974 corners of record I11 1350.71' North and I12 1350.71' South. From the position thus established, I found Mr. Kazianka's monument, a 5/8" rebar with plastic cap #14765 S63E 11.0' distant, which I did not accept for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
7" Cherry N58W 48.51' "1/16S 87"
10" Maple in clump N12E 10.25' do
4" Spruce S17E 52.98' do
Set nail with tag in:
P.Pole #83-20738 #35-5 S65W 58.47'
Bearings are magnetic. Distances are to
nail with tag and are horizontal meas.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 5/25/04

For the Michigan Department of Natural Resources, Office of Land and Facilities