

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

1. Public Land Survey
2. Property Controlling
in Section
3. Miscellaneous
Property in Sec.

Located In: T 42N R 34W
S T R
S T R
S T R
S T R

Corner Code # LM-3 (011)

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:34

L.C. Records: L. 8, P. 138

Gary L. Pisoni

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

East Meander Corner to Sections 1 and 12, T42N, R34W

I, Gary L. Pisoni, in a field survey on March 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on October 7, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Aspen	10"	S 15° E	33 lks (21.78 feet)
Aspen	8"	N 70° E	29 lks (19.14 feet)

PEER GROUP APPROVED

Gary L. Pisoni 12-28-99

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.


Restored the corner position on the East shore of Chicagon Lake which is due West from the Southeast corner of Section 1. The actual meander corner is 924 feet from the Southeast corner of Section 1 which falls in the lake. I set a W.C. M.C. on the East shore of said lake.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 5/8" diameter by 30" long rebar with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T42N, R34W, W.C., M.C., S-1, S-12, West, 39.56', 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Cedar	3"	S 31° E	6.24 feet
Oak	3"	S 30° W	13.25 feet
Cedar	3"	N 21° E	13.07 feet
Steel sign post		N 75° E	0.85 feet



99-138

Signed by

Gary L. Pisoni

Date

12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995