

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 17 T 43N R 31W	PCC between C7 and 1/16 #15, Sec. 17
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/15/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


The Southwest corner of current State of Michigan title within Government Lot 5, Section 17, and
being the Southeast corner of a parcel described in a conveyance State of Michigan to Lawrence Alto,
dated Aug. 22, 1979. The position was not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established the position for the corner according to the description in the 1979 conveyance, at the
intersection of the Section line between Sections 17 and 20 with a line described as beginning at a
point on the North line of Gov't Lot 5 which is 718.8 ft East of the Northwest corner of Gov't Lot
5, thence South and parallel to the West line of Gov't Lot 5 a distance of 1,334.30 ft to the South
line of Gov't Lot 5. The position thus established is 718.80 feet, as measured along the Section
line, east of Section corner C7, and is 189.47 feet west of a monument described in Liber 8 of LCR,
Page 315, Iron County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" R.Pine N18°E 25.3' mrkd "PCC BT"
14" R.Pine S50°E 2.85' do
11" R.Pine N83°W 8.0' do
5" W.Spruce N28°W 37.8' do
Set sq'd cedar post adjacent.
E= 7905805.893 N= 148873.393



Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
Coord. Ref.=NGS PID RL0240: N= 145070.957 m. E= 7907633.635 m.

Signed by Stephan J. Szyszkoski Date 07/18/2013
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division