

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 30 T 43N R 32W	1
	S T R	(GCDB 120300)
	S 30 T 43N R 32W	3
3. Miscellaneous Property in Sec.	S T R	(GCDB 100260)
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 12/22/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 30) West 1/16 corner between Sections 19 and 30. Established in 1968 by A.O.Enger RLS on line between A9 and B9 and 20 chains, proportionate to the original record, west of B9. Set 1"ID I.pipe with 4" alum. cap. W.Birch 4" S41°E 67.03'; Aspen 5" N7 1/2°E 36.38'.

(3-Sec. 30) North 1/16 corner between Section 30 T43N-R32W and Section 25 T43N-R33W. Found no record of prior monumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 30) Found the 1968 monument in good condition and at the record position. The 1968 witnesses were not found. Accepted the monument as a careful and faithful establishment of the position of the corner.

(3) Found a 5/8" dia. Rebar set flush with the ground with 3.2' tall metal fence post immediately adjacent. The position of the rebar is substantially midway and on line between corners A9 and A10 and I accept same as a careful and faithful establishment of the position of the corner. Drove a MDNR plastic cap on the found rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
4" Sugar S40°E 15.55' mrkd "1/16S BT"
5" Sugar S76°W 28.65' do
6" Sugar N34°W 46.55' do
5" Sugar N25°E 41.75' do
Set sq'd cedar post adjacent.
E= 7894703.786 N= 147388.482

(3) Found 5/8" rebar, flush. Set plastic MDNR cap atop same. Set measuring nail with MDNR tag in the side of:
9" Sugar N15°E 33.15' mrkd "1/16S BT"
12" Sugar S29°E 83.05' do
7" J.Pine N66°W 50.35' do
Power Pole 74-2557 S39°W 33.3'
E= 7894291.698 N= 146992.001

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref. (adjusted)=NGS PID AA8081: E= 7895147.463m N= 147176.691m

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/28/2016

For the Michigan Department of Natural Resources, Forest Resources Division

