

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 12 T 43N R 33W	3
	S 12 T 43N R 33W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 08/09/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 12) North 1/16 corner between Sections 11 and 12. Not monumented in the original survey.
The GLO plat for this township gives a distance of 20.01 chains to this corner from Section corner K3
and shows the entire mile K3-K5 as 80.04 chains. The Quarter corner on the west line of the Section
was not established in the original survey.

(2-Sec. 12) East 1/16 corner between Sections 1 and 12. 2002 - Established by J.H.Moore PS 28423
midway and on a straight line between Quarter corner L3 1311.79' west and Section corner M3 1311.79'
east. Set capped rebar.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 12) Established the corner 20.01 chains proportionate distance south of Section corner K3 and
on the Section line. This corner is thus 1335.55' south of K3 and 4006.62' north of K5. From the
position for the corner, I found a 5/8" rebar, not of record, 43.28' south, which I did not accept as
marking the position for the corner.

(2-Sec. 12) Found a 5/8" rebar with J.H.Moore cap substantially at the record position and accepted
same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" Maple S47E 22.3' mrkd "1/16S BT"
8" Balsam S19W 46.3' do
8" Maple in clump N20W 50.2' do
4" Maple N06W 39.4' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(2) Ed. 5/8" capped rebar.
Set measuring nail with MDNR tag in the side of:
12" W.Birch N68E 9.5' with old blaze
9" Balsam S88W 8.3' do
5" Balsam S37E 16.6' mrkd "1/16S BT"
8" Poplar N48W 13.8' do
Set sq'd Cedar post adjacent.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/21/2011

For the Michigan Department of Natural Resources, Forest Management Division



16723

16724