

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

93 DEC 29 PM 2:21
L.C. RECORDS L.C. P. 361

Gilbert Stetson
REGISTER OF DEEDS

For corners in

Iron
(County)

Located In:

Corner Code =#

1. Public Land Survey

T 43N R 33W

J, K-1

#001

T 44N R 33W

J, K-13

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

East Meander Corner S-35, T44N, R33W
S-2, T43N, R33W

I, Gary L. Pisoni, in a field survey on December 20, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor in 1846.

Original corner: Wood post

Original bearing tree:

Hemlock

14"

N 67 1/2° E

27 links (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 1"x30" iron pin located on the East/West wire fence line and 5' from waters edge. Corner position has been used and accepted as the corner locally, for many years. Layed iron pin next to aluminum rod monument as described below. Monument is 3" above ground surface.

This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


At the corner position, I set a 3/4" outside diameter by 3 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T44N, R33W, M.C., S-35, S-2, T43N, 1993, R.L.S. 27457; from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Balsam	3"	N 57° E	13.89 feet
Popple	11"	S 69° E	36.12 feet
Red Maple	7"	S 49° E	58.32 feet
White Birch	12" dbl	S 15° W	13.86 feet
Steel sign post		East	1.10 feet

Signed by Gary L. Pisoni

Date 12-28-93

Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983