

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 33W	G2
	T R	(GCDB 400640)
	T R	
2. Property Controlling in Section	S 3 T 44N R 33W	10
	S T R	(GCDB 400620)
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4	3		2				
3													
4		7		8		9	10		11				
5													
6		18		17		16	15		14				
7													
8		19		20		21	22		23				
9													
10		30		29		28	27		26				
11													
12		31		32		33	34		35				
13													

I, Stephan J. Szyszkoski, in a field survey on 10 02/24/15 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G2) Quarter corner common to Sections 3 & 4. 1984 - Remonumented by K.L.Sackett, RLS by
proportionate measurement to the original record between Section corners north and south. Set
1"IDx32" I.Pipe with 4" alum. cap. 10" Spruce N62°W 86.7'.

(10-Sec. 3) South 1/16 corner between Sections 3 and 4. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G2) Found the 1984 monument in good condition. The 1984 NBT was not recovered. Found the monument
to be on line between Section corners 2642.18' south and 2568.59' north (GLO record = 40.33 1/3 ch.
and 39.19 1/3 ch., respectively), substantially at the position of record. I accepted the monument
as a careful and faithful reestablishment of the position of the original corner.

(10-Sec. 3) Established the position for the corner midway and on the Section line between Section
corner 1321.09' south and Quarter corner 1321.09' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G2) Found 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Poplar N05°E 14.75' mrkd "1/4S NBT"
9" Poplar N81°E 9.8' do
9" Poplar S29°W 18.3' do
6" Poplar N85°W 21.6' do
Set sq'd cedar post adjacent.
E= 7889753.872 N= 162801.377

(10) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
12" Cedar S40°W 22.4' mrkd "1/16S BT"
4" Maple N63°W 22.7' do
4" Maple N02°W 13.9' do
6" Balsam N56°E 16.45' do
Set sq'd cedar post adjacent.
E= 7889746.429 N= 162398.846

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/17/2015

For the Michigan Department of Natural Resources, Forest Resources Division

