

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S <u>7</u> T <u>45N</u> R <u>31W</u> _____ S <u>7</u> T <u>45N</u> R <u>31W</u> _____ S _____ T _____ R _____ S _____ T _____ R _____	B4 14 _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		5		5		4		3		2		1	
3													
4		●		8		9		10		11		12	
5			●										
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on B4 01/01/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B4) Center of Section 7. Not established in the original survey.

(14-Sec. 7) South 1/16 corner between Sections 7 and 8. 1993 - Established by the undersigned midway
and on the Section line between Section corner south and Quarter corner north. Set 1"IDx32" I.pipe
with 4" alum. MDNR cap. 7" Spruce S68W 11.7', 9" Spruce S34E 19.3', 8" Maple N08W 37.6', 7" Spruce
N67E 36.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(14-Sec. 7) Recovered the 1993 monument in good condition and at record bearing and distance from the
1993 witness trees. The BT Maple NW is now a dead stub. Left the monument in place and made new
witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" Maple N02E 30.8' mrkd "C1/4 BT"
4" W.Spruce N19E 44.2' do
4" Poplar S83E 3.9' do
5" Poplar S42W 12.0' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(14) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" Spruce N68E 37.2' w/overgrown blazes
13" Spruce S35E 19.8' do
12" Spruce S70W 11.8' do
8" Maple N47W 34.3' mrkd "1/16S BT"
A sq'd Cedar post found adjacent.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/03/2011

For the Michigan Department of Natural Resources, Forest Management Division



16680

16681

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1971

Revised Oct., 1995