

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	E12
	T R	(GCDB 300140)
	T 45N R 31W	D11
2. Property Controlling in Section	S T R	(GCDB 240200)
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/17/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Hemlock 12" S20°W 18 links, Y.Birch 8" N35°W 17 links.

(D11) Quarter corner common to Sections 29 and 32. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.09 chains east and west. Set Cedar post. Fir 8" N20°E 22 links, Fir 8" S6°3W 20 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2621.07' north and south.

(D11) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2642.20' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
4" Spruce N01°E 22.55' mrkd "1/4S NBT"
4" Balsam S83°E 16.25' do
5" W.Birch S02°W 21.7' do
6" Balsam S60°W 2.9' do
Set sq'd cedar post adjacent.
E= 7907428.756 N= 164126.421

(D11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
6" Balsam S05°W 25.35' mrkd "1/4S NBT"
3" Maple S68°W 12.5' do
3" Balsam N55°W 10.6' do
6" Spruce N12°W 18.25' do
Set sq'd cedar post adjacent.
E= 7906638.065 N= 164939.099

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/04/2015

For the Michigan Department of Natural Resources, Forest Resources Division

