

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Jackson Co

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>27</u> T. <u>1</u> S., R. <u>2</u> E.		<u>I-11, H-11</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-11 SE Cor. Sec. 27

Fd. 15" W. Oak fence post surrounded by stones in old E-W fence line, rotted off at water line; Replaced with 4" x 10' plastic pipe with 1" iron pipe and alum. cap inside and filled with concrete.

H-11 S $\frac{1}{4}$ Cor. Sec. 27

Fd. 3/4" pipe at intersection of fences East-West and South. Replaced with 4" x 36" conc. mon. w/alum. cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 SE Cor. Sec. 27

4" x 10' plastic pipe with 1" iron pipe and alum. cap inside and filled w/conc., stone and conc. around pipe.
S22°W - 9.03' - 12" leaning R. Oak, spike & tag
S70°E - 7.84' - 10" leaning R. Oak, spike & tag
N53°E - 34.45' - 7" Hickory, spike & tag
N 4°E - 70.17' - 18" R. Pine, spike & tag
in swamp @ w. end ditch to East.

H-11 S $\frac{1}{4}$ Sec. 27

4" x 36" Conc. mon. w/alum. cap
S20°E - 18.40' - 14" Hickory, spike
S 3°E - 41.70' - 24" Twin,
Hickory, Spike
S43°W - 37.60' - 6" R. Oak, Spike
S65°W - 33.40' - 10" R. Oak, Spike
All wit. trees are old
witnesses w/large spikes in trees.

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET