

JACKSON COUNTY
APPROVED LAND CORNER

P.A. 343 of 1990

Chairman

Date June 9, 1999

For corners in
JACKSON

(County)

Located In:

Corner Code ~~44~~

SURVEY &
REMONUMENTATION

MAR 13 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

1. Public Land Survey

T 1S R 2E

D-8

T R

T R

T R

2. Property Controlling
in Section


S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R



Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

ALAN L. SCHEPPELMAN

JUNE 11

98

I, in a field survey on , 19 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POINT NOT SET IN ORIGINAL GOVERNMENT SURVEYS.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	13	14	15	16	17	18	19	20	21	22	23	24	
9													
10	20	21	22	23	24	25	26	27	28	29	30		
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THE CENTER OF SECTION WAS ESTABLISHED BY INTERSECTING THE EAST-WEST 1/4 LINE WITH A LINE PROJECTED THROUGH A 2' DIAMETER CONCRETE POST FROM THE NORTH 1/4 POST. THE POSITION OF THE CENTER OF SECTION AGREES WITHIN 0.5' FOR MEASUREMENTS TO PROPERTY CORNERS AND THE EAST 1/4 POST. SET A 4" x 30" CAST IRON HARRISON MARKER STAMPED "D-8 T1S R2E LS 35998" IN THE NORTH SHOULDER OF THE ROAD AT THE TOP OF BANK, 0.4' BELOW THE SURFACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" x 30" CAST IRON HARRISON MARKER WITH BRASS CAP STAMPED "D-8 T1S R2E LS 35998" - 0.4' BELOW GROUND IN NORTH SHOULDER OF ROAD.
NORTH CENTERLINE OF 1" STEEL BAR IN TOP OF 2' DIAM. CONC POST 10.97'
N70°E SET NAIL & TAG 35998 SE SIDE OF POWER POLE 100.66'
S01°E SET NAIL & TAG 35998 EAST SIDE OF 15" HICKORY 87.52'
SOUTH CENTERLINE OF EAST-WEST ROAD 15.15'
N11°W SET NAIL & TAG 35998 EAST SIDE OF 8" RED OAK 94.56'
SOUTH SURVEY MARKER SIGN POST 40.60'



Signed by

Alan L. Schepelman

Date

07/08/98

Surveyor's Michigan License No.

35998