



8 0 6 6 1 6 4
Tx:4046122
2/5/2018 3:50:00 PM

DOCUMENT # 3139120
STATE OF MICHIGAN
KALKASKA COUNTY
RECORDED: 02/05/2018 4:11 PM
PAGES: 2
RECORDING FEES: 30.00
JOANN DEGRAAF
REGISTER OF DEEDS
BK: 4 PG: 28

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson Field Survey Date: April 5, 2017
For corner(s) in: Kalkaska County

Original Public Land Survey Corner					Corner Code
S	21, 22	T	25N	R 5W	G8
S		T		R	
S		T		R	
S		T		R	
Property Controlling Corner					Corner Code
S		T		R	
S		T		R	
S		T		R	
S		T		R	
Property Corner					Corner Code
S		T		R	
S		T		R	
S		T		R	
S		T		R	
Protracted Public Land Survey Corner					Corner Code
S		T		R	
S		T		R	
S		T		R	
S		T		R	

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12	4						
5													
6	18	17	16	15	14	13	6						
7													
8	19	20	21	22	23	24	8						
9													
10	30	29	28	27	26	25	10						
11													
12	31	32	33	34	35	36	12						
13	A	B	C	D	E	F	G	H	I	J	K	L	M

Part A: Corner History

G8 – ¼ corner common to sections 21 & 22, T25N, R5W

- 1852 – GLO – set quarter section post.
- 1) Y Pine 10" S38°W 30 lks.
- 2) Y Pine 14" N16°E 35 lks.

- 1981 – LCRC – L. 2, P.299 – E. Farrier, PS #24594
- set ½" rod on West edge of trail road. S.P.
- 3) N26°E 76.60' 9" R. Pine
- 4) N58°E 36.12' 8" R. Pine
- 5) N81°E 31.14' 9" R. Pine
- 6) S20°E 82.14' 6" J. Pine
- 7) West 1.00' 6" W. post

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

G8 – ¼ corner common to sections 21 & 22, T25N, R5W


Found ½" rebar & cap #24594 12' West of centerline sand road. Found accessories #3, #4, #5 & #7 fitting position of rebar. Accepted the found ½" rebar as a careful and faithful reestablishment of the position of the original corner, and replaced it with a stamped 4" DNR aluminum cap on a 1" x 36" long galvanized iron pipe.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

G8 – ¼ corner common to sections 21 & 22, T25N, R5W

a stamped 4" DNR aluminum cap on a 1" x 36" long galvanized iron pipe. – Set blue post 2' West.

N21°E 76.47' to set nail & tag in SE. side 16" R. Pine
N55°E 35.98' to set nail & tag in SE. side 13" R. Pine
N83°E 31.02' to set nail & tag in N. side 17" R. Pine
S40°E 87.95' to set nail & tag in SW. side 6" J. Pine
N58°W 33.54' to set nail & tag in NE. side 14" J. Pine



Certifying Surveyor's Name

February 1, 2018

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

