

## 86

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


B-5			C-6		
Fd. D.N.R. Mon.	added ced.	post			
12" Tamrack	N42°E	24.17	Drove 1 1/4" x 18" solid Iron rod in ctr.		
29" R. Pine	N82°E	29.35	N-S gravel rd.		
8" J. Pine	S47°W	14.16	P. Pole	S80°W	32.87
17" R. Pine	N85°W	94.3	21" J. Pine	N72°E	77.1
* = Old Wits			8" Maple	S15°E	217.1
			Set ced. post w/Loc Tag	West	33'

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 10 Established south 1/8 corner on West line of Sec.8 equidistant & on line between SW & W1/4  
corner of S-8. Corner falls in approx. ctr. of N-S gravel road.
- 15 Established West 1/8 corner on South line of Sec. 8 equidistant & on line between SW &  
S 1/4 corner of S-8.
- B-5 Fd. Dept. Monument (M. Schaaf 1940-K.Ostling 1956-Richards & Assoc. 1975) with Fargo 1"  
pipe (1912) along side same. Good original Govt. Corner.
- C-6 Established E1/4 Cor. of Sec. 18 midway & on line btw. fd. SE Cor. S-18 & NE Cor. S-18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10			15		
Drove 5/8" x 36" rerod w/R.L.S. cap (buried)			Set 5/8" x 36" rerod w/R.L.S. cap & ced. post		
9" R. Pine	N77°W	75.2'	w/Loc tag		
5" W. Pine	S54°W	100.0'	11" Cherry	S30°E	95.7
9" Cherry (Triple)	S38°E	73.5'	5" J. Pine	S40°W	35.8
Set ced. post w/Loc E.		33'	11" J. Pine	N54°W	61.7
Tag			Ctr. P.Line (NW-SE)	West	180'±
			Ctr. P.Line (NW-SE)	South	110'±

SURVEYOR'S MICHIGAN REGISTRATION NO.



GARFIELD TOWNSHIP (Central Part)  
KALKASKA COUNTY