



DOCUMENT # 3133418
STATE OF MICHIGAN
KALKASKA COUNTY
RECORDED: 01/05/2017 2:39 PM
PAGES: 2
RECORDING FEES: 30.00
JOANN DEGRAAF REGISTER OF DEEDS
BK: 4 PG: 15

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson

Field Survey Date: September 29, 2016

For corner(s) in: Kalkaska County

Original Public Land Survey Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner

Corner Code

S	27	T	25N	R	07W	6
S	26, 27	T	25N	R	07W	7
S		T		R		
S		T		R		

Property Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Protracted Public Land Survey Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2	6		5		4		3		2		1			2
3														3
4	7		8		9		10		11		12			4
5														5
6	18		17		16		15		14		13			6
7														7
8	19		20		21		22		23		24			8
9														9
10	30		29		28		27		26		25			10
11														11
12	31		32		33		34		35		36			12
13														13

Part A: Corner History

6 – NE 1/16 corner section 27

7 – N 1/16 corner common to sections 26 & 27

– None

– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

6 – NE 1/16 corner section 27

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

7 – N 1/16 corner common to sections 26 & 27

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

6 – NE 1/16 corner section 27

a stamped 2" aluminum cap on 5/8" x 34" rebar

N55°E 40.13' to set nail & tag in SE. side 17" W. Pine
S53°E 2.67' to set nail & tag in SW. side 9" Spruce
S72°W 38.52' to set nail & tag in S. side 13" W. Pine
N04°W 28.23' to set nail & tag in W. side 15" W. Pine


Set blue post with location tag 1' North

7 – N 1/16 corner common to sections 26 & 27

a stamped 2" aluminum cap on 5/8" X 34" rebar

N70°E 59.28' to set nail & tag in N. side tri. 14" R. Maple
S14°E 5.83' to set nail & tag in S. side 11" R. Pine
N78°W 21.60' to set nail & tag in N. side 7" R. Pine
N20°W 28.49' to set nail & tag in W. side 10" R. Pine

Set blue post with location tag 1' North


Certifying Surveyor's Name

January 5, 2017

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

