

DOCUMENT # 3133415
STATE OF MICHIGAN
KALKASKA COUNTY
RECORDED: 01/05/2017 2:39 PM
PAGES: 2
RECORDING FEES: 30.00
JOANN DEGRAAF REGISTER OF DEEDS
BK: 4 PG: 12

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson

Field Survey Date: April 22, 2016

For corner(s) in: Kalkaska County

Original Public Land Survey Corner

Corner Code

S T R
S T R
S T R
S T R

Property Controlling Corner

Corner Code

S 13 T 26N R 06W 10
S 13 T 26N R 06W 11
S T R
S T R

Property Corner

Corner Code

S T R
S T R
S T R
S T R

Protracted Public Land Survey Corner

Corner Code

S T R
S T R
S T R
S T R

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7											●	●		7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

10 – S 1/16 corner common to sections 13 & 14, T26N, R6W

11 – SW 1/16 corner section 13, T26N, R6W

– None

– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

10 – S 1/16 corner common to sections 13 & 14, T26N, R6W

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

11 – SW 1/16 corner section 13, T26N, R6W

Set stamped 2" aluminum cap on 5/8" X 34" rebar per BLM standard procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

10 – S 1/16 corner common to sections 13 & 14, T26N, R6W

a stamped 2" aluminum cap on 5/8" x 34" rebar

N65°E 27.28' to set nail & tag in NW. side 18" Maple clump
S02°W 71.37' to set nail & tag in W. side 9" W. Pine
S63°W 24.83' to set nail & tag in SE. side 4" Maple
N70°W 20.21' to set nail & tag in SW. side 4" Ironwood


Set blue post with location tag 1' Northwest

11 –SW 1/16 corner section 13, T26N, R6W

a stamped 2" aluminum cap on 5/8" X 34" rebar

N04°E 26.25' to set nail & tag in a triple 9", 14", 19" maple
N80°E 31.21' to set nail & tag in S. side 8" Maple
S02°E 7.02' to set nail & tag in W. side 7" Maple
N68°W 38.59' to set nail & tag in NE. side 5" Maple

Set blue post with location tag 1' Northeast


Certifying Surveyor's Name

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601

January 4, 2017

Date

