

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN  
RECEIVED

1993 DEC 22 PM 1:30

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 22, 19 93,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


E-8 cor. common to Sec. 20 & 21, T27N-R7W  
1850 GLO re-survey: set post, Cedar 12" N49W, 16; Fir 08", S20E, 16.  
5-52, A.L. Dragoo, Co. Surv., 1" iron Bar w/ accessories.  
4-1-69, M.A. Koivisto, M.S.H.D. fd 3/4" iron bar surv. for M-66.  
10-17-72, J.L. Wilcox, used cor. Liber 1 Pg 243 of Surv.  
8-12-77, J.L. Fletcher, fd bolt spike in Mon. Box, Liber 2 Pg 52 of Surv.  
8-30-78, J.L. Fletcher, fd bolt spike in Mon. Box, Liber 2 Pg 247 of Surv.  
11-9-78, LCRC Liber 2 Pg 132.  
3-2-89, LCRC Liber 2 Pg 372.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 cor. common to Sec. 20 & 21, T27N-R7W  
Found boat spike in Mon. Box 0.8' E. of C/L M-66, w/ accessories. GLO  
witnesses fell in road fill.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a  
careful and faithful reestablishment of the position of the original  
corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 cor. common to Sec. 20 & 21, T27N-R7W  
Found boat spike. Pulled spike and replaced w/ 5/8"x18" re-rod w/ Brass  
Cap.  
N61W, 34.55', 6" W. Birch fd.  
N20, 69.07', 14" Ch. Elm (dead) fd.  
West, 36.22', 6" W. Birch (dead) fd.  
S55W, 46.92', 8" Poplar.  
N89W, 33.06', 1/2 re-rod w/cap fd.  
N71E, 33.24', P. Pole.



Signed by *Eugene Farrier*

Date 12-22-93

Surveyor's Michigan License No. 24594