

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>28</u> N. <u>0.</u> R. <u>5</u> W. <u>0.</u>	<u>L-9, M-8, M-9</u>
2. PROPERTY CONTROLL- ING IN SECTION_____	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-9 Recovered Dept. Mon from previous Dept. Survey (1951); said Corner being a perpetuation of M. Schaaf Cor. which was set from Original B.T.'s sites,
- M-8 Set D.N.R. Mon. equidistant & on line btw. fd. Sec, Cor's, to N & S. Note: M. Schaaf Mon.(set in error) is N65°43'E, 50.8'. Schaaf position per his wits. would be N69°22'E, 62.6'.
- M-9 Recovered Dept. Mon. from previous Dept. Survey (1951) said Mon, being a perpetuation of M. Schaaf Cor. which was set from U.S. B.T. sites,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9	M-8	M-9
Fd. Dept Mon. & Set ced.post	Set DNR Mon. & ced. post	Fd. Dept. Mon. & ced. post
5" R.Pine N66°W 47.0'	22" W.Pine N51°W 129.4'	W/Loc. Tag.
8" R.Pine N29°E 33.2'	5" R.Pine N47°E 23.4'	22" R.Pine S15°W 90.47'
7" R.Pine S32°E 23.8'	28" W.Pine Stp. N85°E 21.3'	24" R. Pine S36°E 108.28'
8" Cherry Stp. S12°W 33.2'	4" R.Pine S50°E 27.3'	7" Cherry S60°E 49.25'
E-W gravel rd. Due S. 62'±		Ctr. E-W gravel rd. South 51'±
		Ctr. Trail rd, North East 13.5'

SIGNED BY

Carl F. Roser 2-5-78

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

CHIEF OF SURVEY PARTY


DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLUE LAKE TOWNSHIP
KALKASKA COUNTY