

OCT 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 AUG 24 AM 11:52

For corners in

COMMISSION

Kent

(County)

Located In:

Byron Twp.
Corner Code #

1. Public Land Survey

T 5N R 12W

D-10

T R

cen. sec. 29

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

W. J. Glaza
REG. OF DEEDS

6968

Register of Deeds Stamp & File Number

I, Wallace E. Glaza, in a field survey on August 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. No. 212 (Exxel)

Found 3/4" iron - checks with previous witnesses

- 1) Nail in side T-pole SW 62.93'
- 2) NW corner of house SE 94.55'
- 3) Nail in side 8" Mulberry WNW 46.83'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-10 (Center of Section 29, T5N, R12W, Byron Township, Kent County, Michigan)

Found iron pipe over leaded stone. Verified iron pipe to be at the intersection of the 1/4 lines. Accepted iron pipe as center of Section. Replaced iron pipe with standard Kent County Monument

- West 1/4 corner to center - 2624.15'
- North 1/4 corner to center - 2648.91'
- East 1/4 corner to center - 2684.43'
- South 1/4 corner to center - 2659.17'

P.A. 345 1990 KENT COUNTY


PEER APPROVED 7/28/94

CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 (Standard Kent County Monument)

- 1) Remon tag & nail in N side 14" Mulberry N80°W 47.34'
- 2) Remon tag & nail in E side 8" Maple N20°W 98.91'
- 3) Remon tag & nail in W side 26" Spruce S20°E 88.68'
- 4) SW corner of foundation (House No. 9570) N20°E 209.44'
- 5) Centerline North-South road West 3.5'



Signed by

Wallace E. Glaza
Glaza & Associates, Inc.

31592

Date

8-22-94

Surveyor's Michigan License No.