

\$7.00 SEP 13 1995
\$2.00
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>12W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

8614

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 AUG 28 AM 10:51

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehuse, in a field survey on April 11 19 95,
do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required
in the current manual of survey instructions of the United States Department of the interior, Bureau of
Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,
4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered,
found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11	1831	G.L.O. Notes	Mullett	Set Post
	1945	Wit. Map	K.C. Surveyor	Iron in Concrete
	1963	Wit. Map	K.C. Surveyor	Iron in Concrete
	1973	L.C.R.C. #423	Medema, Van Kooten & Assoc.	Found 1" Iron in Monument Box
	1981	L.C.R.C. #1640	Nederveld & Jonker	Found 1" Iron in Monument Box\Set K.C. Monument
	1988	L.C.R.C. #4603	Olson, Meyers & May	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/25/95

CHAIRMAN Harry Huber

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Nederveld &
Jonker on 3/5/81 and was recorded per L.C.R.C. #1640.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found standard Kent County Monument in monument box at C/L intersection of Byron Center Avenue running N-S and 100th
Street running E-W per L.C.R.C.'s #1640 and #4603 as set by Nederveld & Jonker in place of a 1" iron in monument box
which checked L.C.R.C. #423 and K.C. Surveyor's Wit. Map (1963).

L.C.R.C. #1640

Nail & Remon. tag on NE side T. pole S 15° E 87.26'
Nail & Remon. tag on SE side P. pole S 45° W 43.78'
Nail & Remon. tag on NW side T. pole N 35° E 48.28'
SE corner store found N 55° W 62.18'

L.C.R.C. #4603

Nail & Remon. tag on NE side T pole S 15 E 87.
Nail & Remon. tag on SE side P pole S 45 W 43.78'
Nail & Remon. tag on N 35 E 48.10'
SE cor store found N 55 W 62.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence
of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Standard Kent County Monument in a Monument Box


Nail & K.C. remon. tag on NE side T. pole S 15° E 87.29'
Nail & K.C. remon. tag on SE side P. pole S 45° W 43.78'
Nail & K.C. remon. tag on NW side T. pole N 35° E 48.04'
SE cor. store foundation N 55° W 61.39'

Signed by Randy J. Kolehuse

EARTH TECH

Date

8/21/95



Surveyor's Michigan License No. 25854