

SURVEY & REMONUMENTATION

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent
(County)

Located in: Vergennes
Township

Corner Code #

1. Public Land Survey

T 7N R 9W J-9E

T R

T R Witness Monument

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Randy Kolehouse, in a field survey on January 23 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9	1838	G.L.O. Notes	N. Brookfield	Point in River
	1989	L.C.R.C. #5220	John Bueche	Set K.C. Witness Monument
	1995	L.C.R.C. #8246	William Byl	K.C. Witness Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/19/98

CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/10/89 and was recorded per L.C.R.C. #5220.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found a Standard Kent County Witness Monument 42' ± North of the Flat River 388.56' East of J-9 per L.C.R.C.'s #5220 and #8246 as set by John Bueche on the South line of Section 23.

L.C.R.C. #5220

Nail & Remon tag on W side of a group of 5 8"-10" Poplar
S 10° W 26.46'

Nail & Remon tag on SW side 10" Poplar S 20° E 30.92'

Nail & Remon tag on N side 32" Oak S 60° E 13.46'

Nail & Remon tag on E side 8" Ash N 10° E 17.96'

Nail & Remon tag on NE side 16" Maple N 35° W 51.87'

Nail & Remon tag on S side 10" Ash N 75° W 29.07'

L.C.R.C. #8246

Nail & KC Remon. tag W. side group 5 8"-10" Poplar
S 10° W 26.41' (m. 26.43')

Nail & KC Remon. tag SW side 12" Poplar S 20° E 30.92'

Nail & KC Remon. tag N. side 36" Oak S 60° E 13.41' (m. 13.43')

Nail & KC Remon. tag E. side 8" Ash N 10° E 17.90' (m. 17.87')

Nail & KC Remon. tag NE side 18" Maple N 35° W 51.79' (m. 51.84')

Nail & KC Remon. tag S. side 10" Ash N 75° W 29.07' (m. 29.08')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Standard Kent County Witness Monument

Nail & K.C. remon. tag on W side group 5"-10" Poplar S 10° W 26.43'


Nail & K.C. remon. tag on SW side 12" Poplar S 20° E 30.92'

Nail & K.C. remon. tag on N side 36" Oak S 60° E 13.43'

Nail & K.C. remon. tag on E side 8" Ash N 10° E 17.87'

Nail & K.C. remon. tag on NE side 18" Maple N 35° W 51.84'

Nail & K.C. remon. tag on S side 10" Ash N 75° W 29.08'



Signed by Randy J. Kolehouse

Date 12/19/98

Surveyor's Michigan License No. 25854