

**SURVEY &
REMONUMENTATION**

MAY 09 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent
(County)

Located In:

Corner Code //

1. Public Land Survey

T 10N R 11W

North witness

monument to J-3

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No.

Recorded Plat

5. Private Claims

I, Wallace E. Glaza, in a field survey on August 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration
No previous history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


North witness monument to J-3, T10N, R11W, Solon Township, Kent County, Michigan.

Set standard 4" x 30" Harrison Monument on a straight line between the center of Section 2 and the computed location of J-3, 1479.20' South of the center of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

North witness monument to J-3 (standard 4" x 30" Harrison Monument)

- | | | |
|--|-------|--------|
| 1) Nail and tag in NW side 10" Poplar | N38°E | 9.18' |
| 2) Nail and tag in E side 18" Elm | S08°E | 30.72' |
| 3) Nail and tag in SE side clump Maple | S48°W | 47.58' |
| 4) Nail and tag in S side 10" Poplar | S75°W | 12.68' |
| 5) Nail and tag in W side 10" Poplar | S27°W | 9.90' |
| 6) South edge of field | North | 20'± |



Signed by

Glaza and Associates, Inc.

Surveyor's Michigan License No.

31592

Date

8-17-93