



LC-000096
Page: 1 of 1
12/29/1999 10:07A
BK-2 Pg-549

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in RICHLAND TOWNSHIP
KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey

T 1S. R 10W. G-13
T R
T R
T R
T R
T R
T R
T R

2. Property Controlling
in Section

S
S
S
S

3. Miscellaneous
Property in Sec.

SURVEY &
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

6. IWM Job No. 32282

I, Allen H. McMachen, in a field survey on November, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1827 - John Mullett, D.S., Set post. Corner to Secs 33 and 34, Wh. Oak 10" N. 59° E. 52 lks., Wh. Oak 10" N. 87° W. 46 lks..
1887 - F. Hodgman, C.S., "Found old stake hole 131 lks. West of corner of Secs 3 and 4, T. 2 S., R. 10 W., Set post. Hickory 4" S. 68½° W. 90 lks., Hickory 5" N. 18° 50' W. 45 lks..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found empty monument box at grade. Removed box and found a second monument box with an I.W.M. iron inside. Second box was 1 foot North of the first box. Dug below found iron and found clay tile 3.5 feet below grade 0.1' South and 0.1' West of surface iron location.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-18-1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a 20" Harrison Monument over clay tile with monument box over, Accessories:

Placed iron rod N. 55° W. 34.13'
Placed iron rod S. 65° W. 33.71'
Placed iron rod N. 70° E. 49.40'
Placed iron rod S. 65° E. 49.26'
In centerline East & West road



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/17/99