SURVEY & REMONUMENTATION

1	
n .	

Property in Sec.

APR 2 7 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE t 74, Mich. P.A. 1970

_	Filing Requirement of Ac
or corners in	

Kalamazoo			_ocated in:	Corner Code ##		
C	(County) limax Township					
	Public Land Survey		T3 S R 9 W	<u>J-7</u>		
			T R	<u> </u>		
			T R			
			T R			
2.	Property Controlling	s	T R			
	in Section	\$	T R			
3.	Miscellaneous	S	T R			

LIBER


Register of Deeds Stamp & File Number

_ , Recorded Plat . 5. Private Claims

. 1

Robert E. Snell , in a field survey on ... June 8 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



North

1826: U.S. Government Survey; Set 1/4 Section Post.

15" Lynn 14" Beech

East

50°

West

22 | ks 35 Lks

F. Stimson, County Surveyor; Planted stake and stone. 1864:

F. Hodgman, County Surveyor; Stone of former survey removed. From one witness tree, set new stone (6" x 6" x 24") and noted, Blk Walnut 6" North 52° West 84 Lks Blk Walnut 5" South $37\frac{1}{2}$ ° East 111 L

Blk Walnut 5" South 37½° East 111 Lks

10

F. Hodgman, County Surveyor; Put a 1' earthen post underneath and restored the stone to B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: its' place.

Found a large (6" x 6" x 24") rectangular stone over 1' of 3" round tile beneath. Found an iron at 6.2' North and 0.9' East of tile.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 7-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 Post Section 14, T. 3 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on $July^2 \chi$, 1994. Found 3" round tile beneath stone as called for in 1883 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed stone and placed a 30" Harrison monument and monument box over tile.

Center Line "Q" Avenue			North			1.5'
PK Nail in Northeast Side	23"	Tulip	South	55°	East	51.93'
PK Nail in Northeast Side	31"	Walnut	South	30°	East	69.40'
PK Nail in North Side	29"	Maple	South	60°	West	61.07'
PK Nail in West Side	14"	Hickory	North	10°	West	41.04'
Center Line 45th Street			East			6.5'

2. July

9734

Surveyor's Michigan License No.