

# SURVEY & REMONUMENTATION

FEB 08 2000

Sequence #1

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2PAGE

452

CLERK - REGISTER

*Handwritten signature*

99 FEB 11 PM 1 08

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

### SECTION

For corners in

Kalamazoo (County)	Located In:	Corner Code#
Wakeshma Twp.		
1. Public Land Survey	T 4S R 9W	D-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary D. Hahn, in a field survey on October 29, 1998  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner  
points mentioned in lines 1 and 2 above were in conformance with regulations and rules  
therefore as required in the current manual of survey instructions of the United States  
Department of the Interior, Bureau of Land Management or by a decree of a Court of Law  
and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance  
with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;  
established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

#### A. Description of original monument and accessories and/or subsequent restoration:

1826 - Quarter post established by U.S. Deputy Surveyor Robert Clark, Jr.  
Beech 7" N 4°E 26 lks. Beech 10" S 84°W 2½ lks.

1866 - F. Stimson "Gov. corner lost. Established midway between A & C. Set long pointed flatish stone, top 2 or 3 inches out of ground. Charcoal  
near top of stone". Gives distance of 40.215 CH. - 2654.19' to SE. & SW. corners.

#### KCRC Witness Ties:

12" - 14" Twn. Maples S 79.40  
Iron S 45°W 91.05'

#### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.

1998: No surface marker found. Excavated 6' (N & S) x 12' (E & W) x 7' deep hole centered on bisection. Found a 1" x 2" wood stake standing erect  
at a depth of 4.5' just below old road bed. Found no evidence of stone. Stake in line with tree line & fence line to south. Stake was 4.3± N 45°E of  
bisection. Reestablished corner at the bisection of the previously ratified southwest and southeast corners of section 17.

#### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


D-7, South Quarter Post, Section 17, Town 4 South, Range 9 West. Ratified by the Kalamazoo County Remonumentation Peer Group on December 17,  
1998. Set a 30" Harrison Monument in a monument box at the above described bisection. This position is accepted as a careful and faithful  
reestablishment of the position of the original corner.

#### Witness Ties:

Set Mag. Nail in 12" Maple S 5°E 41.71'  
Set Mag. Nail in R.R. tie fence post South 29.55'  
Set ½" rebar @ edge of asphalt N 20°W 19.96'  
Set ½" rebar @ edge of asphalt N 47°E 22.91'

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12-17-1998**

*Handwritten signature*



Signed by *Handwritten signature*  
Surveyor's Michigan License No. 38116

Date 02/09/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,

JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995