

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 18 N. R. 12 W.	D-7; E-9
2. PROPERTY CONTROLLING IN SECTION 20	T. 18 N. R. 12 W.	1; 12
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 31, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. (continued)

12
Set 5/8" X40" re-rod.
6" B.Oak N43°W 22.3
7" Maple S53°W 39.7
Set Ced. Post w/loc tag.
Due E 33'
Fn. Cor. (Fn N&E)
Due E 26'
ctr. N-S gr. rd. Due E 8'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-7 Fd. & accepted Ir. that fits G. Johnson Wit. Corner falls in rd. intersection E-W-S. Johnson survey dated 1931.

E-9 Re-stored Sec. Cor. per Geo. H. Johnson survey in E 1/2 of Sec. 20, dated 1931; double distance & line across fd. Johnson's E 1/4 & S 1/8 on E line, Sec. 20. Also see B, item 2, Sec. 28, Code.

1 Fd. rod, 3'± N. of approx ctr. of E-W gravel road.

12 Restored S 1/8 Cor. on N-S 1/4 line, Sec. 20, per G. Johnson survey dated 1931. Fd. one old Johnson Wit. & fence E&W. Fits straight N-S 1/4 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7

E-9

Fd. 5/8" Ir. Rod
14" R. Pine N05°E 36.57
10" W. Pine N55°E 64.78
Power Pole S25°E 61.51
Set Ced. Post w/loc. tag
Due N 33'

Set DNR Mon. & Ced. Post
14" Maple N25°W 34.7
5" & 8" Maple N20°E 63.9
10" Maple S28°W 50.7
Rand W Due N 33'
Rand N Due E 8'
N-S Trail Due W 76'

1
Fd. 5/8" iron rod
6" W. Oak N15°W 48.2
8" W. Oak S50°W 37.4
Set Ced. post w/loc. tag
Due N 33'
Fd. Axel shaft w/gear (removed
Same) S28°03'E 5.70
Old Fn. Cor (E&S)
Due S 33.0

SIGNED BY

Carl F. Roser 5-15-78

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY


CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE



(SEAL)

CHERRY VALLEY TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO.