

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>20</u> N. S. R. <u>12</u> W.		M-3; L-1; M-1; M-2
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ N. S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JUNE 29, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

1. CONTINUED

XX

M-1

M-2

SET DNR MON & CED POST  
 10" R. OAK S80°E 6.3'  
 13" R. OAK S30°E 29.8'  
 3" W. PINE S40°W 31.5'  
 FD 1 1/2" X 1 1/2"  
 ANGLE IRON S81°54'E 102.66'

SET DNR MON & CED POST  
 5" R. PINE N10°W 44.7'  
 3" R. PINE N20°E 19.3'  
 4" R. PINE N70°E 19.8'  
 CTR OLD N-S GRADE DUE W 17' ±  
 CTR E-W GRAVEL RD DUE N 183' (±2')

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 M-3 RE-ESTABLISH SEC COR COMM TO SEC'S 1 & 12, T20N-R12W & SEC'S 6 & 7, T20N-R11W ON LINE & AT PRO-RATED DISTANCE TO U.S. BETWEEN THE NE COR OF S-1 & THE E 1/4 COR OF S-12.  
 L-1 RE-ESTABLISHED N 1/4 COR S-1 MID-WAY & ON LINE BETWEEN NW & NE COR'S OF S-1. FD CED POST W/ USFS LOC TAG MARKED N 1/4 S-1, S65°W, 23'. AN OLD FN COR (STANDING), FN REMAINS W,S,E, (FAINT IS 21'-W & 11'-S).  
 M-1 RE-ESTABLISHED NE COR OF S-1, T20N-R12W (ALSO NW COR OF S-6, T20N-R11W) AT PRO-RATED DISTANCE TO U.S. (60.36 CH. E OF COR TO T21N-R11 & 12W) ON SOUTH LINE OF S-31, T21N-R11W. SEE WORKING DRAWING, SHEET 2 OF 4. FD CED POST W/USFS LOC TAG, S15°W, 16.5'. E-W TRAVERSE LINE IS 18' SOUTH.  
 M-2 RE-ESTABLISHED 1/4 COR COMM TO S-1, T20N-R12N & S-6, T20N-R11W ON LINE & PRO-RATED DISTANCE TO U.S. BETWEEN THE NE COR & THE SE COR OF S-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3

L-1

SET DNR MON & CED POST  
 30" W. PINE S55°W 125.4'  
 3" R. PINE N10°E 37.2'  
 4" R. PINE S55°E 60.2'  
 CTR N-S BIT TOP RD  
 STARTING TO CURVE  
 NW'LY WEST 25'

SET DNR MON & CED POST  
 7" S. MAPLE S75°E 38.4'  
 8" S. MAPLE S25°E 18.3'  
 9" S. MAPLE S45°W 11.2'

SIGNED BY

Carl F. Roser 04-06-82

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

CHIEF OF SURVEY PARTY


DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

LAKE COUNTY