

SURVEY & REMONUMENTATION

1993

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lapeer
(County)

Located in:

Corner Code #

1. Public Land Survey T 10N R 12E M-10
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED FOR RECORD

93 DEC 22 PM 3:00

LIBER 5 FILE NO. 29
Lapeer
Lapeer

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10. East quarter corner Section 25. History: East town lines run by Joseph Wampler, 1821. Page 670 North west and south lines run by Hervey Parke 1833 page 667. Subdivision of township run by Hiram Burnham, 1834. page 667 Witnesses Ash 5 S11 W .13 Cedar 9 N10 W .7 set post. County Surveyors Record: Nothing. Recorded surveys Nothing. Unrecorded surveys Kay 3/26/85 30-10-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Slightly rolling farmland Cade Road(gravel) Maynard Road(gravel) to west fence to east 33' south. Low swamp area fill several feet deep. Set 1/2 " Iron with Brass cap on line north & south at centerline of road to west. Fence to west 1284' north, ditch to west 1345' south. MEASUREMENT M-10 TO M-11 2639.27 M-10 TO M-9 2573.27 M-10 TO A-10(10-13) 33' SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 11, 1993
Set 1/2 " Iron with brass cap, on line north & south at centerline of road to west;
N 51°W 38.26' N. END 30" C.M.P.
S 63°W 35.50' S. END 30" C.M.P.
N 82°W 110.89' NAIL & TAG N. SIDE 14" ASH
S 64°W 99.60' NAIL & TAG N. SIDE 14" ASH
SOUTH 33.00' 1/2" IRON



Signed by [Signature] Date 12-02-93

Surveyor's Michigan License No. 23510