

JAN 10 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 392
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

14 DEC 1999 4:34:02 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S30 & 31 T - 5 - S R - 3 - E	6
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. This corner not established by original government surveyors
1980 Wemer Sommer did a survey of the SW 1/4 of Section 30 and set a iron pipe at the intersection of the centerlines of Pentecost Hwy. and Reed Road and a line between the SW corner & S 1/4 corner of Section 30
1996 Michael Bartolo found 3/4" iron pipe in the pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 9, 1999 I found the iron pipe under base course of asphalt. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040. Set monument box to be level with final course of asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box .

MAG nail & re-mon tag in EP East 35.68
MAG nail & re-mon tag in EP S 5° E 279.17
MAG nail & re-mon tag in EP N 85° W 261.03
MAG nail & re-mon tag in EP N 30° W 73.16

SW corner Section 30 (3/4" iron pipe recorded in Liber 2, Page 83) West 1903.97
S 1/4 corner of Section 30 (iron pipe recorded in Liber 2, Page 85) East 3241.79



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 7, 1999

Signed by Glenn E. Richard Date Dec. 8, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040