

**SURVEY &  
REMONUMENTATION**

**JAN 15 1998**

**SECTION**

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 1 PAGE 215**

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey

T - 8 - S R - 3 - E

M-4

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec

S T R

S T R

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

17 OCT 97 3:56 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**\*NOTE: SEE COMMENTS & SKETCH ON BACK**

G.L.O. 1824 John Mullett ran a corrected town line from the south and set 1/4 Section post 4.85 chains North of the old 1/4 post by Joseph Wampler W. Ash 7 N 30 W 19 W. Ash 4 S 12 W 27  
Couldn't find any information about this corner in Blair's or J.L. Richard's records.  
1970 Werner Sommer re-established this corner using the found R.R. spike located A-4 T8S, R4E and recorded it in L 2, P 185.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 30, 1997 I found a 60d spike over the iron pipe set by Werner Sommer.  
Oct. 8, 1997 Replaced spike over iron pipe with 3/4" X 3' iron pipe capped G.E.R. 13040 and set monument box in base course of new asphalt pavement

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.  
Found dbl. hd. nail & aluminum disc in 28" Ash S 20° W 66.04  
Found dbl. hd. nail & Aluminum disc in E.P. S 20° E 81.77  
Survey mark spike & re-mon tag in E.P. N 20° E 108.06  
Survey mark spike & re-mon tag in 16" Cedar N 85° E 97.24  
Iron pipe in monument box at A-4 T8S R4E South 272.72



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Oct. 14, 1997  
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993